

QUAD status New testbox

Fred Hartjes NIKHEF

Nikhef/Bonn LepCol meeting September 3, 2018

the state of the s

Brief examination new InGrids

Received August 7

- 30 chips class A
- 16 chips class K, R, F for testing, dummies etc

Some grids look bit messy

 Occasional delamination of part the broad dyke at the wirebond side





Under the microscope

- Grids look under the microscope even better than on photographs
 - Irregularities seen on the photographs originate from minor delaminations from the pillars
 - Height deviations $5 7 \,\mu m$
 - > only limited effect on gas gain
- Conclusion: as far as can be seen from the first superficial inspection all class A and B chips can be used



Status QUAD production


- Delay because of movement to another cleanroom (H070)
 - Vacuum, compressed air, internet to the assembly PC
- QUAD 10 (damaged flex) will be used to make demo using class K,R, .. Chips
- **QUAD** 11
 - Mostly done
 - Leak tight (< 1 ml/min)
 - Low O2 diffusion (< 30 nl/min)
 - Ref: at the present laser chamber we have 27 μ l/min
- **QUAD 12**
 - Being assembled
- **QUAD 13**
 - Assembly started



Assembly sheet QUAD 11

Task	Date done	Comment
Read PCB ID	30-8-2018	1802430000006
Remove notch of LV connector	20-8-2018	
Attach ID labels	29-8-2018	
Close guard holes and make M1.2 thread	23-8-2018	
Measure COCA dimensions	28-8-2018	39.584; 28.388
Machine wirebond PCB to size	22-8-2018	
Assemble QUAD mechanics	20-8-2018	
Remove glue traces, mount HV wires	22-8-2018	
Make QUAD gastight	23-8-2018	
Check gas-tightness (and O2 leak)	27-8-2018	< 1ml/min; < 5 ppM@6 ml/min
Mount thermal tape	30-8-2018	
Align chips	30-8-2018	1: W23-G9 2: W23 J9 3: W23G10 4: W23 K6
Position verification	31-8-2018	
Wire bonding		
Electrical test		
Glue HV wires (Traduct)		
Glue HV wires (araldite)		
HV test in air		


(nominal COCA dimensions: 39.600; 28.380)




Laser setup single QUAD

Still operational

- Occasional data taking
 - Kees L
 - Naomi?
- Problem: O2 and moisture diffusion
 - O2 diffusion ~ 1600 ppM @ 16.7 ml/min
 - Scales inverse proportional with flow
 - => 27 μl/min
 - Cause not understood (flex feed through?)
- May be cleaned with O2 filter
 - 150 ml capacity
 - => 93 h running @ ~ €180
- Moisture diffusion
 - 65% => 27% RH (~ 6000 ppM)
 - Affects drift velocity




Design 2 x 4 testbox ready



Testbox in production


- Mechanics ready ~ mid September
- Glass plates orderedExpected mid October
- Power board for concentrator ordered??



Bonn testbeam Preliminary time schedule

Preparation


- September 17 start making model setup at Nikhef
- September 26 start packing
- October 2 (Tuesday) travel to Bonn, unloading
- October 3 installation
 - Access??
- October 4 6 (Thursday Saturday) data taking
- October 7 (Sunday) loading car, travel home



Testbeam issues

- Do we need a refreshment of the safety course?
 - Last one was in June 2017
 - Peter needs a full safety course
- How about planned access periods?
- Are there other experiments installed on the same experimental table?
- Are we the main user?
- Can we integrate our detector with the Mimosa telescope?
- Fred will travel one day in advance to Bonn to inspect the area
 - Preference September 17 23





Testbeam issues (ctnd)

- Adjusting the detector in the beam
 - 17.8 cm above table plane
- Which degrees of freedom do we want?
 - **X**, Z

- Remote, no accuracy
- Horizontal rotation
 - (Too) small rotary table
 - Remote, bit wobbly
- Vertical rotation
 - Goniometer

Participants

- Fred
- Gerhard?
- Harry?
- Jan
- Kees
- Kevin?
- Peter
- People from Bonn?



