


Remarks about the October testbeam



Nikhef/Bonn LepCol meeting October 8, 2018


Lacking


- We did not made up a data taking plan in advance
 - Mechanics: which degrees of freedom do we want?
 - Goniometer and rotary stage were not used
 - Setup would be simpler if we omitted them
 - But we needed a readout of the Z movement, too late to implement
- We did not determine a good working point for the QUADs
 - 300 V grid voltage does not give a good single electron efficiency
 - => significantly reduced number of hits per track
 - 330 V is much better
 - We wanted a much higher field voltage than before $(280 \Rightarrow 450 \text{ V/cm})$
 - The HV circuit did not permit that completely ($\leq 400 \text{ V/cm}$ @ 330 V grid)



To be improved


- Next time we should bring a setup with two scintillators with us
 - Working point determined in advance
 - Noise cancelling by coincidence
 - Measuring t0 jitter
- Telescope
 - Maybe Nikhef should provide an optical bench for the second telescope half
 - Remote X-Z movement





To be improved cntd

- Telescope
 - Maybe we should provide an optical bench for the second telescope half
- Easier to have the leak tray higher (table level)
 - Easier to install
 - Shorter cables/tubing
 - Still well below the beam (70 vs 138 cm)
- Alignment
 - Hindered because beam dump point was not visible



QUAD 3

Two QUADs

- Damaged grids
 - Easy to identify the chips
- Problematic HV connections
- QUAD 11
 - Grids practically undamaged
 - Minor irregularities visible
 - May not affect the gas gain much
 - Reliable HV connections
 - Guard ~150 µm too high on one side (solder point)



