
MYRRHA

and its

driver accelerator










NNV (astro-)particle physics – fall meeting, November 2025

Fission generates high-level radioactive waste




1 ton of nuclear fuel used 4,5 year in commercial PWR reactor produces electricity for 100,000 Belgian families per year (3500 kWh/y per family)



After 4,5 years the spent nuclear fuel contains:


- 94,7% of resources we can recycle (U+Pu)
- 5,1% of nuclear waste with low radiotoxicity (FP's)
- 0,2% of high radiotoxicity nuclear waste



Fast neutrons for transmutation


- Fission of minor actinides
- Resulting in radio-isotopes of lower radiotoxicity

 Dominant cross-section for fission requires fast neutrons



Accelerator Driven System (ADS)

LINEAR ACCELERATOR (600 MeV)



ADS reactor: rather a necessity than a virtue

- Both critical reactors and ADS can be used as transmutation systems
- Nevertheless, a big load of MAs can jeopardize the control of a critical reactor because of:
- 1) Reducing delayed neutron fractions, β (due also to the reduction of ²³⁸U) and reduced margin to prompt criticality ($\rho = \beta$)

$$\psi(\mathbf{r},t) = \psi_{o}(\mathbf{r}) \sum_{m=0}^{M} A_{m} e^{\omega_{m}t}$$

$$T = \frac{1}{\rho} \left[\frac{1}{K_{eff}} + \sum_{i=1}^{M} \frac{\beta_{i}}{\lambda_{i}} \right]$$
Characteristic period of the reactor

2) Doppler feedback reduced with increasing amount of MAs

The ADS can transmute big loads of MAs without losing safety and this solution is needed for heavily MA loaded core (>10%)




6 |


ADS inherent safety – by design principles

- Subcritical operation
- Nuclear chain reaction sustained by the accelerator beam power: the accelerator stops, the reactor 'stops'.
- In case required, turning off the accelerator (beam) immediately puts the reactor in a safe state as the nuclear reaction dies out.

- Remaining ADS heating power significantly lower than in conventional FR
- Sufficient self-cooling can be designed, based on natural circulation of the coolant by gravity between the cold Heat Exchanger (HX) and the hot core



Shared & efficient solution for Minor Actinides management EU case with 144 power reactors using EFIT 400 MWth



→ 15 EFIT with each 400 MWth required for all EU HLW treatment

Doel (BE) = 9000 MWth Tihange (BE) = 9000 MWth

Core safety parameters limit the amount of MA that can be loaded in the critical core for transmutation. Possible transmutation rates:

- FR: 2 to 4 kg/TWh
- ADS: 35 kg/TWh (based on a 400 MW_{th} EFIT design)





MYRRHA

7 September 2018



The **Belgian Federal Government** announce its **decision to**:

- Description
 De
- Establish governmental support for promoting MYRRHA international partnership
- Establish the MYRRHA international not-for-profit organization (Founded in 2022)



MYRRHA International non-profit organisation

MYRRHA AISBL: separate legal entity to welcome external partners/investors

Responsibility:

SCK CEN

- Design & build MINERVA
- Conduct R&D for phases 2
 ACC-600 & 3 MYRRHA
 Reactor
- Obtain licenses for Phase 1 and later on for Phases 2 & 3
- Being the nuclear operator of MYRRHA/MINERVA

MYRRHA

- Establish the MYRRHA International Consortium
- Guarding the overall scope of MYRRHA program
- Receiving & managing funds for the realization of MYRRHA/MINERVA

- The Belgian Institute for Nuclear Research
- Founded in 1952
- ≈ 950 employees, ≈250 MEuro annual budget
- Reactors for
 - 1/3 of worldwide radio-pharmaceuticals
 - High power semiconductor doping
 - Calibration
 - One just completed dismantling (BR1)
 - One "tiny" one already coupled to a 30keV accelerator (zero-power ADS)
 - •
- ≈ 2 hours drive from Utrecht



ADS demonstrator - MYRRHA's versatility

Less (toxic) nuclear waste




Transmutation reduces the final residual waste **volume** by a factor 100 and natural radiation level is reached after 300 years

Production of medical radioisotopes



Therapeutic radio-isotopes can **fight cancer cells** in a more targeted way with significant reduction of side effects for patient

New reactor concepts



testing by **fast neutrons** for reactors as well as used in

Fundamental research



Deepening understandings in Nuclear physics, atomic physics, fundamental interactions, solid state physics & nuclear medicine

MYRRHA reactor


- Conceptual design phase completed
- Commissioning from second half of 2030s

Reactor				
power	65 to 100 MW _{th}			
k_{eff}	0,95			
spectrum	fast			
coolant	LBE			

- Integrated Pool-type concept with LBE coolant
- Fuel assemblies: hexagonal bundles of cylindrical wire-spaced fuel pins (MOX fuel 30wt.% Pu)
- 4x heat exchangers: double-walled with leak detection; water/steam on secondary side
- Bottom core loading: single in-vessel fuel handling machine (IVFHM)

N.B.: similar design (liquid lead fast reactor) can also be used for energy production

'Energy amplifier' introduced by Carlo Rubbia in the 1990s



MYRRHA Reactor Buildings


- Multi-disciplinary integration
 - Reactor Building
 - Nuclear material handling
 - Ex-vessel remote handling
 - Hot Cells
 - Building Equipment
 - HVAC
 - Utilities
 - Process
 - 1&C
 - Electrical
 - Fire protection
 - Accelerator
 - Spent Fuel Building
 - Waste Building



MYRRHA Facilities for R&D support for Design & Safety



MYRRHA, a phased approach



MYRRHA Licensing status: where are we?

- MYRRHA Phase 1: MINERVA Licensing
 - License for construction & operation for the class IIA MINERVA installation obtained in November 2022
 - Preparation of testing plan and list of HP&WPs for phased construction & commissioning of nuclear safety relevant structures, systems and components (2024-2027)
- MYRRHA Phase 3: Reactor Pre-licensing
 - End 2024 the pre-licensing was finalized
 - FANC issued the final report to the Belgian Government, on the licensability of the MYRRHA reactor.
- MYRRHA Phase 2: Extension of the Accelerator to 600 MeV
 - Extension of the MINERVA license conditional to the opinion of the Belgian Government on the reactor licensability

ACCelerator requirements

Protons

> 600 MeV

- MW class average beam power
 - mA CW beam current
 - duty factor adaptation
- Reactor cycle operational schedule
 - MYRRHA: 90 day cycle
 - industrial ADS: quasi continuous

- High reliability
 - no beam interruption > few s
 - to avoid thermal stress on reactor components

- High availability
 - To get uptime


- Cost/Energy efficiency (CAPEX/OPEX)
 - Industrial approach

Options & worldwide efforts

- SC-Linac:
 - MYRRHA 1st stage (100 MeV) in implementation
 - CiADS in implementation
 - JADS design study
 - •
- Cyclotron
 - Transmutex company design study
 - TEXAS A&M university design study for stacked cyclotrons
 - •

Option 1: Cylotrons


- Existing cyclotrons reach MW
- Several design studies




psi.ch



transmutex.com



A. Sattarov et al, IPAC'2012




Th. Stammbach, "Proposal for 10MW cyclotron"

sck cen

Option 2: Superconducting linacs


- CiADS in implementation
- MYRRHA 1st stage (100 MeV) in implementation
- Multiple design studies



sck cen


MYRRHA - accelerator key design decisions

- 17 MeV normal conducting injector
 - Parallel redundancy
- Superconducting linac (100/600 MeV)
 - 3 types of SC cavities, operated at 2K
 - Significant RF-power overhead for serial redundancy/availability
- Use of solid state amplifiers




sck cen

Injector front-end







Pantechnik Monogan 1000 LEBT

2 solenoids opticsgas injection for SCC2 Allison emittancemeterselectrostatic chopperACCT


4 rod RFQ up to 160kW


Rebunching section

Injector front-end commissioned


RFQ commissioned with 95% transmission in nominal conditions

Nominal energy: 1.494 ± 0.003 MeV





17 MeV Injector




176 MHz normal conducting RF
4-rod RFQ with up to 160 kW to 1.5 MeV
2 Quarter-wave resonators
15 accelerating + 2 rebunching CH-cavities
RFQ & Cavity design by IAP/Bevatech
CH-cavity production started at RI


30 keV ECR-DC-proton source (Pantechnik)


LEBT: 2 solenoids, chopper & BD

Super-conducting (SC) linac


- Optics & layout "classic high-power SC-linac-style":
 - 30 cryo modules with each 2 single spoke cavities (352.2 MHz, β = 0.352)
 - Warm section with doublet & diagnostic
 - BPM & correctors integrated into quadrupoles
- Last doublet used to match into "HEBT"
- Significant RF-overhead for serial fault tolerance
- Matching optimization still ongoing







Cryomodule components
















MGS - magnetic shield




Helium BUFFer




Support

Cryomodule

Cross section



Internal Components




Reliability in MYRRHA accelerator


- Design choices
 - Linear accelerator
 - Injector: parallel redundancy
 - SC linac: serial redundancy installing RF overhead
 Fast de-tuning of SC cavities
- Reliability model
 - in collaboration with CERN
 - using AvailSim4

Injector reliability - AVAILSIM4 simulations

- ✓ Availability of the linac simulated with Monte Carlo code (AVAILSIM4)
- ✓ AVAILSIM4 result for the redundant injector strategy:




- target failure rate per hour for the injector deduced from breakdown of estimated individual failure rates for all components
 - Failure rate/h simulated for
 - different Mean Time Between Failures (MTBF)
 - different Mean Time To Repair (MTTR)



scl: cen | scl

SC-LINAC: Dynamic RF-compensation



✓ The plot shows power requirements for all cavities from a pure beam dynamics point of view, when 4 neighboring cavities compensate 1 faulty cavity

QM supply chain

Cavity [CAV]

Coupler [CPLR]

Tuner System [TUN]

Magnetic Shield [MGS]

Cryostat [QMST]

5x manufacturing tenders

QM-assembly tender

Cryomodule [QM]

Assembly tender



QM Prequalification at FREIA

Cryomodule [QM]


Collaboration activity Collaboration

Installation


Internal activity























Contractor

To be awarded

CE construction





- Started in 2024
- 2027 rain/wind tight

From 2027

• installation of general infrastructure

From 2028

• Accelerator installation





Timeline – phase 1

Nuclear licensing: approval received from authorities

11/2022 2016 2024 2030 2020 2028 Beam Design Construction Commissioning


- Phase 2 and 3 implemented beyond 2030
- Reactor commissioning planned from 2037





Full Power facility


Beam dump for testing LINAC reliability, Fusion-material irradiation with p & n











ISOL@MYRRHA systems

under advanced prototyping









LINAC components Under manufacturing



Injector


ITS Constructed & tested in LLN, Transfer for reassembly in Mol



ISOL@MYRRHA systems




Modular design 2 Project Agreements




Floor-space and services available for installing experimental setups

ISOL@MYRRHA – Applications & users


Fundamental nuclear physics



Innovative Medical Isotopes



Solid-state physics



 Emerging infrastructure recommended in NuPECC Long Range Plan



• Emerging infrastructure in **PRISMAP** (access platform with leading institutes in the supply chain for European biomedical researchers)



Status ISOL systems

Advancing the technical design

Basic design of ISOL@MYRRHA systems either completed/advancing

Prototyping


- ISOL system offline constructed, operational
- Isotope-Collector station under tests
- TISA & RDS under manufacturing
- Target Module constructed
 - -> ARIEL front-end (collab. TRIUMF)

1st separated ion beam



R&D program

@ SCK CEN & external labs






R&D infrastructure at SCK CEN

- ISOL@MYRRHA labs
 - ISOFF
 - Material & Thermal test systems
 - IMRILS lab
- Materials-research laboratories

ISC: Restricted

ISOL@MYRRHA off-line system commissioned in Labo 2



41 ISC: Restricted


Day-1 yields at ISOL@MYRRHA


Targets chosen for day-1:

- SiC
- Ti
- ThO₂
- UO₂

Ion Sources for day-1:

- Surface Ion Source
- Laser ionization
- (FEBIAD)






Available: Report with all day-1 user yields from the above plot! (In the CERN Box folder used for the project agreements)


Day-1 targets


Produce ^{22~28}Al & ^{23~29}Mg from Si- or Ti-based targets



Leading material candidate SiC

Cross section verification






General good agreement

Preliminary Yield

In target production rate [#/uC]							
²⁴ Al	²⁵ Al	^{26g} Al	²² Mg	²³ Mg			
8 10 ⁷	4 10 ⁹	5 10 ¹⁰	2 10 ⁸	4 10 ⁹			



Esimated Yield [#/uC]					
²⁴ Al	²⁵ Al	^{26g} Al	²² Mg	²³ Mg	
6 10 ²	3 10 ⁴	7 10 ⁹	2 10 ⁶	1 10 ⁸	

Microstructure analysis*



Revealed powder grain agglomerates

*SiC powded from CERN (collab. on SiC target material)

International R&D network (1)

Universities



























































Exploring a better tomorrow




















































International R&D network (2)







Copyright © SCK CEN

PLEASE NOTE!

This presentation contains data, information and formats for dedicated use only and may not be communicated, copied, reproduced, distributed or cited without the explicit written permission of SCK CEN.

If this explicit written permission has been obtained, please reference the author, followed by 'by courtesy of SCK CEN'.

Any infringement to this rule is illegal and entitles to claim damages from the infringer, without prejudice to any other right in case of granting a patent or registration in the field of intellectual property.

SCK CEN

Belgian Nuclear Research Centre

Foundation of Public Utility

Registered Office: Avenue Herrmann-Debrouxlaan 40 – BE-1160 BRUSSELS Operational Office: Boeretang 200 – BE-2400 MOL